JUNE 5, 2026
REHABILITATION OF BRIDGE NOS. 00058 & 03563
FEDERAL AID PROJECT NO. N/A
STATE PROJECT NO. 0102-0372
TOWN OF NORWALK

ADDENDUM NO.1

This Addendum addresses the following questions and answers contained on the "CT DOT QUESTIONS AND ANSWERS WEBSITE FOR ADVERTISED CONSTRUCTION PROJECTS":

Question and Answer No. 5

SPECIAL PROVISION(S)
NEW SPECIAL PROVISION

The following Special Provision is hereby added to the Contract:

- ITEM NO. 0603053A – REPAIR GOUGED EXISTING STEEL

CONTRACT ITEM(S)
NEW CONTRACT ITEM

ITEM NO.	DESCRIPTION	UNIT	QUANTITY
0603053A	REPAIR GOUGED EXISTING STEEL	EA	3

PLAN(S)
REVISED PLANS

The following Plan Sheets are hereby deleted and replaced with the like-numbered Plan Sheets:

- 02.01.A1
- 04.08.A1
- 04.28.A1

The Bid Proposal Form has been revised to reflect these changes.

The Detailed Estimate Sheets do not reflect these changes.

There will be no change in the number of calendar days due to this Addendum.

The foregoing is hereby made a part of the contract.

ITEM #0603053A - REPAIR GOUGED EXISTING STEEL

Description: Work under this item consists of grinding gouges, nicks and shallow cracks in existing steel smooth as shown on the plans.

Materials: None.

Construction Methods: Each area to be repaired shall be verified by the Engineer. No work shall be performed without the approval of the Engineer. Proposed equipment for the grinding operations shall be approved by the Engineer.

Repair of nicks, gouges, and shallow cracks shall be accomplished by grinding to fair, or blend, the notches to the adjacent undamaged steel. A fairing slope of 10:1 in the longitudinal direction shall be obtained. When a fairing slope of 10:1 cannot be achieved due to interferences with the grinding area, a minimum fairing slope of 5:1 in the longitudinal direction may be allowed with the Engineers approval. Grinding shall be performed in the longitudinal direction.

After grinding is complete, the ground area shall be tested with magnetic particle testing (MT) to confirm any potential cracks have been removed from the damaged area.

Grinding and testing shall be performed before the existing steel is painted.

Method of Measurement: This work will be measured for payment by the actual number of areas repaired, tested and accepted.

Basis of Payment: This work will be paid for at the Contract unit price each for "Repair Gouged Existing Steel," which price shall include grinding and testing of the repair, and all material, equipment, tools and labor incidental thereto.

Pay Item	Pay Unit
Repair Gouged Existing Steel	ea.