MATERIAL SYMBOLS

- BRICK
- MASONRY BLOCKS
- CONC.
- PRESENT WALLS
- NEW WORK IN PRESENT BLDG. (MATERIALS TO MATCH PRESENT)

FYR-FYTER EXTINGUISHER CAB. MODEL #ABO WITH FLOT TRIM. DUO PANEL DOOR & D.S.A. GLASS PANEL. EACH CAB. SHALL HAVE MODEL 94-23 FYR-FYTER EXTINGUISHER

ELEVATION TYPICAL FIRE EXTINGUISHER CABINET 1½"=1'0"

5"x5"x⅜" STEEL ANGLE PRINTED & BOLTED TO WALL ALL SIDES PROVIDE ½" HOLES @ 2'0" C. FOR BOLT

MULTI-PURPOSE ROOM & FLOOR DETAIL ¾

121'-10"

89'-10"

49'-2"

32'-0"

24'-0"

40'-8"

23'-5"

CHAIN LINK FENCE

SLOPE TOP OF RETAINING WALL

CLASS ROOM #18

CLASS ROOM #19

CORRIDOR #20 ELEV. FL. 99'-0"

BOYS' TOILET #21

GIRLS' TOILET #22

TEACHERS #23

STORAGE #24

PRESENT KITCHEN #25

STORAGE #26

STORAGE #27

STAIR HALL #2

STAIR HALL #11

REINF. CONC. STAIRS WITH 1½" GALV. STEEL HAND RAILS PAINTED

BUS STOP CONC. PLAT FORM

PRESENT DOOR TO REMAIN

BRICK UP PRESENT OPENING, FINISH TO MATCH PRESENT

PROVIDE NEW OPENING AS SHOWN, SLIDER, REMOVE PRESENT OPENING AS REQUIRED. MATERIALS & FINISH TO MATCH PRES.

CHANGE SWING OF PRESENT DOOR

PRESENT DOORS TO REMAIN

EXISTING CAFETERIA #31

CORRIDOR #32 FL. ELEV. 99'-0" ±

PRESENT LALLY COL.

USE PRESENT CLASS RM. DOOR

PRINCIPAL'S OFFICE #29

STOR. #33

CLASS #34

PRESENT CLASS RM. #30

CUSTODIAN #33

NURSES OFFICE #34

TEACHERS ROOM

KINDERGARTEN #38

REMOVE PRES. PARTITION

NEW FIXTURES & PARTITION. MATERIALS & FINISH TO MATCH PRES.

LAV. #35

PROVIDE 6 NEW SHELVES

FL. ELEV. 100'-0" ±

EXISTING RAMP DN

REMOVE PRESENT SINK

NEW LAV.

VESTIBULE #40

ALUM. SADDLE

SEE DETAIL D-D

CONC. PLATFORM

CUT PRESENT COUNTER & CABINETS BACK TO 2'-0" DEPTH BEYOND PRES. SINK & DROP SINK, COUNTER TOP @ 2'-6" ABOVE FL.

BLOCK PRES. DOOR, MATERIAL & FINISH TO MATCH PRES.

SEE DETAIL ON THIS SHEET

REMOVABLE METAL MULLION (HARDWARE ALLOWANCE)

COURT 40'-0" x 60'-0"

MULTI-PURPOSE ROOM #27 FL. ELEV. 99'-0"

FAN ROOM ABOVE

GYM STORAGE #28

STEEL STAIRS & ALUM HAND RAILS

FIRE EXTINGUISHER CAB.

DRINKING FOUNTAIN

STAIR HALL #16

72'-4"

70'-9"

17 WINDOWS EQUAL SPACING

PLAN OF WINDOWS, MULTI PURPOSE ROOM

FAN ROOM #36

ALUM. LADDER 22" WIDE, 7'0" x 2½" STRINGERS WITH 1" ROUND PIPE RUNGS - RUNGS TO HAVE MILLED SHOULDERS AND TO BE SET THROUGH STRINGERS & WELDED - RUNGS TO BE 12" O.C. LADDER SHALL BE BOLTED THROUGH WALL TOP & BOTTOM & SHALL BE SECURELY ANCHORED BETWEEN THESE POINTS

ALUM. LOUVER, PANAMA & SCREEN

BUILT UP ROOF

MULTI PURPOSE & FAN ROOM R...

1" = 1'-0"

BRICK

BLOCK

COL. & I-B, A 20.21

GRAVEL STOP

MULTI-PURPOSE ROOM EXPANS... JOINT

1½" = 1'-0"

1'-2"

BRICK

MASONRY BLOCKS

16 GA. I.C.. THRU WALL COP. FLASHING

NEW ROOFING, FLASHING & CRICKET AS REQUIRED

MULTI PURPOSE ROOM

ELEV. 112'-2¾"

BLOCKING

PRES. STEEL JOISTS

NEW MASS.

PRES. MASS.

CAFETERIA

1'-4"

WALL SECTION A-A 1½"=1'0"

"ADDITIONS & ALTERATIONS"
SHERMAN CONSOLIDATED SCHO...
SHERMAN, CONN.

PHILIP N. SUNDERLAND & WILLIAM WEBB SUNDERLAND
ARCHITECTS
DANBURY, CONN.

FIRST FLOOR PLAN

DWG NO. 3 | DATED 12/12/61 | DRAWN
SCALE 1/8"=1'-0" | REVISED 3/26/62 | CHECKED

#20