**EAST WALL STREET – LANDMARK SQUARE**

**CITY OF NORWALK**
**LOTCIP PROJECT NO. L102-0004**
**DESIGN INITIATED CHANGE ORDER NO. 01**
**Date: September 03, 2024**

## Description:

This Change Order (CO) is necessary to avoid installation conflicts and improve constructability for the proposed catch basins/drainage within the project area, due to discoveries during the test pit phase of the project. It was determined that several catch basins would not be constructable as proposed due to known utilities based on digitized base-mapping. Given the need for these changes, it was decided that certain catch basins would be relocated, added, and/or removed to improve the constructability of these structures. The curblines were also reviewed and revised to accommodate any drainage modifications or to provide improved radii on the northeast corner of the intersection of Main Street at Wall Street/East Wall Street, that the City requested be reviewed.

Additionally, grading was reviewed and revised per the City Department of Public Works and to ensure appropriate flow of stormwater to revised catch basin locations.

Finally, the plans were reviewed to ensure the streetscape elements would be consistent with the City's overall view for the project area and the other local roadways.

## CONTRACT ITEMS

### NEW CONTRACT ITEMS

The following Contract Items are being ADDED to the Contract as part of this Change Order Request:

| Item No. | Description | Unit | Quantity |
|---|---|---|---|
| COXXXXX | Precast Concrete Tee Manhole – 0'-10' Deep | EA. | 2 |
| COXXXXX | Convert Catch Basin to Type 'C-M" Catch basin | EA. | 1 |
| COXXXXX | 8" R.C. Pipe – 0'-10' Deep | LF | 15 |
| COXXXXX | Convert Catch Basin to Special Type 'C" Catch Basin | EA. | 2 |

**REVISED CONTRACT ITEMS**

The following Contract Items are being REVISED as part of this Change Order Request:

| Item No. | Description | Original Quantity | Change in Quantity |
|---|---|---|---|
| 0507167 | TYPE 'C-M' CATCH BASIN TOP | 1 EA. | +1 EA. |
| 0586001.10 | TYPE 'C' CATCH BASIN – 0'-10' DEEP | 1 EA. | +1 EA. |
| 0586040.10 | TYPE 'C-L' CATCH BASIN – 0'-10' DEEP | 1 EA. | -1 EA. |
| 0586100.10 | TYPE 'C-M' CATCH BASIN – 0'-10' DEEP | 3 EA. | -3 EA. |
| 0586600 | RESET CATCH BASIN | 2 EA. | -1 EA. |
| 0651634 | 8" CORRUGATED P.E. PIPE (SMOOTH INTERIOR) | 70 LF | -70 LF |
| 0651656 | 12" CORRUGATED P.E. PIPE (SMOOTH INTERIOR) | 15 LF | -15 LF |
| 0651657 | 15" CORRUGATED P.E. PIPE (SMOOTH INTERIOR) | 60 LF | -33 LF |
| 0686000.12 | 12" R.C. PIPE – 0'-10' DEEP (CLASS IV) | 15 LF | +20 LF |

**DELETED CONTRACT ITEMS**

- NONE

## PLANS

**NEW PLANS**

- NONE

**REVISED PLANS**

The following Plan Sheets are being REVISED as part of this Change Order Request:

| Drawing No. | Description |
|---|---|
| REV-01 | List of Revisions |
| HPN-01 | Construction Plan – General Layout |
| GRA-01 | Grading Plan |
| DRA-01 | Drainage and Erosion & Sedimentation Control Plan |
| PRO-01 | Proposed Profile Plan |
| PRO-02 | Proposed Profile Plan |
| TYP-01 | Typical Sections |
| XCS-01 | Cross-Section Plans |
| XCS-02 | Cross-Section Plans |
| XCS-03 | Cross-Section Plans |

| Drawing No. | Description |
|---|---|
| XCS-05 | Cross-Section Plans |
| XCS-06 | Cross-Section Plans |
| XCS-07 | Cross-Section Plans |
| LND-01 | Streetscape Amenities & Planting Plan |
| ELE-02 | Electrical New Work |
| PVT-01 | Pavement Marking & Signing Plan |
| MDS-02 | Miscellaneous Details |
| MDS-05 | Miscellaneous Details |
| MDS-10 | Miscellaneous Details |
| MDS-11 | Miscellaneous Details |
| MDS-12 | Miscellaneous Details |
| TSP-01 | Main Street at Wall Street and Commerce Street at Wall Street Traffic Signal Plan |

**DELETED PLANS**

- NONE