

CITY OF MERIDEN, CONNECTICUT
SCHEDULE OF PRICES FOR THE CONSTRUCTION OF CITY PROJECT NO. B024-22
STATE PROJECT NO. 79-212, FAP NO. H020(001)
REPLACEMENT OF CENTER STREET BRIDGE (BRIDGE NO. 04185) OVER HARBOR BROOK
CITY OF MERIDEN, CONNECTICUT

DATE OF
 BID OPENING January 24, 2024 TIME: 11:00 A.M. NO BIDS WILL BE ACCEPTED AFTER 11:00 A.M. "NO EXCEPTIONS"

Note: --- The bidder shall fill in, under the column "Unit Prices Bid," the unit prices, written in words and in numbers, for which he proposes to perform the various items of work called for, and under the column headed "Amount," the amount of each of the items at the unit price bid. After the proposal is opened and read, the quantities will be extended and totaled in accordance with the written bid prices and the bid will be verified or corrected.

ITEM NO.	ITEM	UNIT	QUANTITIES	FIGURES	WRITTEN	(FIGURES)
0020763	A Disposal of Sediments	Ton	100			
0101000	A Environmental Health and Safety	L.S.	1			
0101117	A Controlled Material Handling	C.Y.	9190			
0101128	A Securing, Construction and Dismantling of a Waste Stockpile and Treatment Area	L.S.	1			
0101130	A Environmental Work –Solidification	Ton	780			
0201001	Clearing and Grubbing	L.S.	1			
0201199	A Remove and Reset Fence	L.F.	385			
0202000	Earth Excavation	C.Y.	3425			
0202100	Rock Excavation	C.Y.	165			
0202200	Channel Excavation-Earth	C.Y.	45			
0202216	A Excavation and Reuse of Existing Channel Bottom Material	C.Y.	150			
0202217	A Supplemental Streambed Channel Material	Est.	1	\$ 15,000.00	Fifteen Thousand Dollars and Zero Cents	\$ 15,000.00
0202315	A Disposal of Controlled Material	Ton	18610			
0202318	A Management of Reusable Controlled Material	C.Y.	400			
0202529	Cut Bituminous Concrete Pavement	L.F.	75			
0203202	Structure Excavation - Earth (Excluding Cofferdam and Dewatering)	C.Y.	4130			
0203304	Structure Excavation - Rock (Excluding Cofferdam and Dewatering)	C.Y.	200			
0204151	A Handling Water	L.S.	1			
0204213	A Handling Contaminated Groundwater	L.S.	1			
0205005	A Trench Excavation 0'-15' Deep	C.Y.	1640			
0205006	A Rock in Trench Excavation 0'-15' Deep	C.Y.	80			
0209001	Formation of Subgrade	S.Y.	1100			
0212000	Subbase	C.Y.	305			
0216000	Pervious Structure Backfill	C.Y.	4070			
0219001	Sedimentation Control System	L.F.	240			
0286001.10	Rock in Drainage Trench Excavation 0'-10' Deep	C.Y.	10			
0406170	HMA S1	Ton	335			
0406171	HMA S0.5	Ton	325			
0406173	HMA S0.25	Ton	15			
0406194	A Joint and Crack Sealing of Bituminous Concrete Pavement	L.F.	75			
0406236	Material for Tack Coat	Gal.	230			
0503001	Removal of Superstructure	L.S.	1			
0586006.10	Type 'C' Catch Basin Double Grate Type 2 (4' Sump) 0'-10' Deep	Ea.	2			

0601062		Footing Concrete	C.Y.	325		
0601064		Abutment and Wall Concrete	C.Y.	255		
0601088	A	Concrete Form Liners	S.F.	555		
0601121		Parapet Concrete	L.F.	35		
0601122		Bridge Sidewalk Concrete	C.Y.	60		
0601502		1/2" Preformed Expansion Joint Filler For Bridges	S.F.	415		
0601541	A	24' X 11' Precast Concrete Box Culvert	L.F.	52.5		
0601542	A	12' X 10' Precast Concrete Box Culvert	L.F.	52.5		
0602030		Deformed Steel Bars-Galvanized	Lbs.	90000		
0602889		Dowel Bar Splicer System Galvanized	Ea.	45		
0602936		Drilling and Grouting Reinforcing Bars	L.F.	160		
0606906	A	Rebuild Masonry Wall	C.Y.	10		
0610002		Drilling Holes and Bonding Dowels	Ea.	60		Deleted item
0686000.12		12" R.C. Pipe (0'-10') Deep	L.F.	30		
0686000.18		18" R.C. Pipe (0'-10') Deep	L.F.	35		
0686000.30		30" R.C. Pipe (0'-10') Deep	L.F.	25		
0686100.15		15" C.C.M Pipe (0'-10') Deep	L.F.	15		
0707001	A	Membrane Waterproofing (Woven Glass Fabric)	S.Y.	175		
0708001		Dampproofing	S.Y.	360		
0714999	A	Monitoring Structures	L.S.	1		
0716000	A	Temporary Earth Retaining System	S.F.	15840		
0717000		Earth Retaining System Left in Place	S.F.	7620		
0728008	A	3/8" Crushed Stone	C.Y.	275		
0755014		Geotextile (Separation - High Survivability)	S.Y.	945		
0813021		6" Granite Stone Curbing	L.F.	280		
0813451		Granite Stone Transition Curbing	L.F.	90		
0815001		Bituminous Concrete Lip Curbing	L.F.	375		
0817006	A	6" X 10" Granite Stone Curbing for Bridges	L.F.	100		
0819002	A	Penetrating Sealer Protective Compound	S.Y.	150		
0822100.01		Temporary Traffic Barrier	L.F.	140		
0904051	A	3 Tube Curb Mounted Bridge Rail	L.F.	100		
0913000		Remove Chain Link Fence	L.F.	210		
0913011		5' Chain Link Fence	L.F.	130		
0921001		Concrete Sidewalk	S.F.	2855		
0922500		Bituminous Concrete Driveway (Commercial)	S.Y.	720		
0924002		Concrete Driveway Ramp	C.Y.	30		
0944000		Furnishing and Placing Topsoil	S.Y.	590		
0950005		Turf Establishment	S.Y.	590		
0969062	A	Construction Field Office (Medium)	Mo.	18		
0971001	A	Maintenance and Protection of Traffic	L.S.	1		
0974001		Removal of Existing Masonry	C.Y.	470		
0975004		Mobilization and Project Closeout	L.S.	1		
0976002		Barricade Warning Light-High Intensity	Day	2160		
0977001		Traffic Cone	Ea.	12		
0978002		Traffic Drum	Ea.	12		
0979003		Construction Barricade Type III	Ea.	14		
0980020		Construction Surveying	L.S.	1		

1206023	A	Removal and Relocation of Existing Signs	L.S.	1		
1208931		Sign Face – Sheet Aluminum (Type IX Retroreflective Sheeting)	S.F.	35		
1209005		Painted Pavement Marking - 4" White	L.F.	235		
1210102		4" Yellow Epoxy Resin Pavement Markings	L.F.	630		
1220027		Construction Signs	S.F.	445		
1301082	A	8" Ductile Iron Pipe (Water Main)	L.F.	280		
1302004	A	8" Gate Valve	Ea.	3		
1303198	A	Hydrant Water Main	Ea.	1		
1303201	A	Relocate Hydrant (Complete)	Ea.	1		
1401246	A	16" Ductile Iron Pipe (Sanitary Sewer)	L.F.	200		
1401260	A	27" Ductile Iron Pipe (Sanitary Sewer)	L.F.	10		
1401261	A	30" Ductile Iron Pipe (Sanitary Sewer)	L.F.	180		
1401675	A	Sanitary Manhole (6' Dia) 10' to 20' Deep	Ea.	5		
1403115	A	Inverted Siphon Inlet Chambers (Sanitary Sewer)	Ea.	1		
1403116	A	Inverted Siphon Outlet Chambers (Sanitary Sewer)	Ea.	1		
1504010	A	Temporary Support of Utilities	L.S.	1		
						TOTAL

NAME OF BIDDER _____
ADDRESS _____
BY: _____
Print or type name _____ Title _____
SIGNATURE _____ DATE _____
TELEPHONE _____ FAX: _____ E-Mail _____