



- PLUMBING DRAWING NOTES:**
- ① 3" DCW, 1-1/2"DHW, 1" DHWR RISERS
  - ② 2" DCW, 1-1/2" DHW, 1" DHWR RISERS
  - ③ 4" S. STACK
  - ④ 4" V. STACK
  - ⑤ 6" RWL, 6" OWRL
  - ⑥ OWRL TERMINATION. COORDINATE EXACT LOCATION AND ELEVATION WITH ARCHITECT.
  - ⑦ (2) 3"G (2 PSI) RISER.
  - ⑧ AT SINK PROVIDE 2"W. DN., 1-1/2" V. UP, 1/2" DCW, 1/2" DHW.
  - ⑨ (2) GAS METER / REGULATOR ASSEMBLY BY UTILITY COMPANY. PROVIDE MAIN GAS SHUT-OFF VALVE. DELIVER PRESSURE TO BUILDING SHALL BE 2 PSI.
  - ⑩ 2" W. UP.
  - ⑪ 3" W. DN.
  - ⑫ 3" W. STACK.
  - ⑬ 3" V. STACK.
  - ⑭ AT SINK PROVIDE 1-1/2"W DN TO 2" WW, 1/2" HW & CW FROM BELOW.
  - ⑮ 1-1/2" V. DN.
  - ⑯ 2" W. STACK
  - ⑰ PROVIDE MOTION DIFFERENTIAL FITTINGS ON ALL PIPING CROSSING EXPANSION JOINTS. REFER TO SPECIFICATIONS FOR INFORMATION.
  - ⑱ 1/2"DCW DROP TO WALL HYDRANT.
  - ⑲ 4"RWL UP TO ROOF DRAIN.
  - ⑳ 4"RWL DN.
  - ㉑ AT SINK PROVIDE 2"W., 1-1/2"V., 1/2"DCW, 1/2"HW. EXTEND 2"W. TO SEDIMENT TRAP.
  - ㉒ 2"W. DN., 1-1/2"V. UP. EXTEND UNDER COUNTER TO SINKS.
  - ㉓ FLOOR C.O. SHOWN FOR REFERENCE ONLY. REFER TO UNDERGROUND PIPING PLAN FOR C.O. & PIPING LOCATION.
  - ㉔ PROVIDE 1" COND FROM COND PUMP AT VRF.
  - ㉕ 4"ORWL UP TO O.R.D.
  - ㉖ FIBER COMMUNICATION ALTERNATE BID. IF ALTERNATE BID FOR FIBER OPTION IS ACCEPTED, CONDENSATE IS TO BE REMOVED.
  - ㉗ HEAT TRACE CONTROLLER FOR CANOPY ROOF DRAIN HEAT TRACE CABLE.

drawing title PLUMBING LEVEL 1 PLAN		STATE OF CONNECTICUT DEPARTMENT OF ADMINISTRATIVE SERVICES	
professional seal	REVISIONS		
	mark	date	description
	1	08/25/19	ADDENDUM #3
drawing prepared by	BVH INTEGRATED SERVICES 206 WEST NEWBERRY ROAD BLOOMFIELD, CT. 06002		date 08/16/2019
	project SCSU NEW HHS BUILDING 501 CRESCENT STREET NEW HAVEN, CT 06505		scale 1/8" = 1'-0"
CAD no.	project no. BI-RS-329	drawn by MT	approved by JSC
			drawing no. P1.01